

2019 Opening Prices

Above Ground

With a cover & a cleaning	\$345
With a cover – no cleaning	\$270
Without a cover & a cleaning	\$320
Without a cover – no cleaning	\$245

Above ground pool openings include: inspecting the pool area for any winter damage; remove any cover water if approved by the customer (\$100 charge); remove and clean both sides of the winter cover, water tubes (if applicable), and air pillow; store the winter supplies where the customer instructed; check the water level of the pool and start water if needed (we do NOT leave the water running after we leave the job unless specifically instructed by the customer); remove the plugs from the returns and skimmer; install the ladder and/or steps; install & adjust the eyeballs for proper circulation of the water; replace the filter drain cap; replace the pump plugs, lubricate the pump cover o-ring, replace the pump basket, and prime the pump; hook up the chlorinator (if applicable), lubricate the cover o-ring, hook up the offline hoses, and replace the plugs; install the new Nature 2 cartridge (additional charge for cartridge), lubricate the o-ring, and set the installation date; set the filter valve to the Filter position; if the water level is at operating position, start the pool up and check for leaks; clean the pool if approved by the customer; check and add appropriate chemicals (if it has a salt system, it takes at least 24 hours for the chlorine to read on the digital read out once the system has been started back up. We recommend that you bring in a water sample after the pool has been open a couple of days. We will balance the pool with shock and tablets. You are responsible for purchasing and adding the salt.); put the automatic cleaner in and check the operation; and clean the deck off by blowing or spraying.



In Ground

With a cover & a cleaning	\$450
With a cover – no cleaning	\$375
Without a cover & a cleaning	\$375
Without a cover – no cleaning	\$295

In ground pool openings include: inspecting the pool area for any winter damage; remove any cover water if approved by the customer (\$100 charge); remove and clean both sides of the winter cover and water tubes (if a safety cover, we take the springs off the anchors and set the anchors flush into the pool deck); store the winter supplies where the customer instructed; check the water level of the pool and start water if needed (we do NOT leave the water running after we leave the job unless specifically instructed by the customer); remove the plugs from the returns and skimmer; install the ladder and handrail (if it is left out or accessible); install & adjust the eyeballs for proper circulation of the water; install the filter drain cap; install the pump plugs, lubricate the pump cover o-ring, intall the pump basket, and prime the pump; hook up the chlorinator (if applicable), lubricate the cover o-ring, hook up the off-line hoses, and install the plugs; install the drain plug on the heater; install the new Nature 2 cartridge (additional charge for cartridge); set the filter valve to the Filter position (sand & DE filters); if the water level is at operating position we start the pool up and check for leaks; clean the pool if approved by the customer; check and add appropriate chemicals (if it has a salt system, it takes at least 24 hours for the chlorine to read on the digital read out once the system has been started back up. We recommend that you bring in a water sample after the pool has been open a couple of days. We will balance the pool with shock and tablets. You are responsible for purchasing and adding the salt.); put the automatic cleaner in and check the operation; start-up the heater if instructed by the customer (electric heat pumps only – we do NOT light the pilot light on gas heaters); and clean the deck off by blowing or spraying.